Western Technologies Inc.

GEOTECHNICAL EVALUATION REPORT

LISBON CHANNEL TRAIL
Southern Boulevard to Tarpon Avenue
Rio Rancho, New Mexico
WT Reference No. 3227JJ055

PREPARED FOR:
Wilson & Company, Inc.
4900 Lang Avenue NE
Albuquerque, New Mexico 87109
Attn: Tyler J. Ashton, P.E.

February 23, 2017



Jeff M. Boyd, P.E.
Senior Geotechnical Engineer

Reviewed By: Bruce M. MacIlroy, P.E.
Technical Director

TABLE OF CONTENTS

1.0 PURPOSE **1**

2.0 PROJECT DESCRIPTION **1**

3.0 SCOPE OF SERVICES **1**
3.1 Field Exploration 1
3.2 Laboratory Analysis 2
3.3 Analyses and Report 2

4.0 SITE CONDITIONS **3**
4.1 Surface 3
4.2 Subsurface 3

5.0 GEOTECHNICAL PROPERTIES & ANALYSIS **3**
5.1 Laboratory Tests 3

6.0 RECOMMENDATIONS **3**
6.1 General 3
6.2 Lateral Design Criteria 4
6.3 Pavements 5

7.0 EARTHWORK **5**
7.1 General 5
7.2 Site Clearing 5
7.3 Foundation Preparation 6
7.4 Pavement Preparation 6
7.5 Materials 6
7.6 Placement and Compaction 7
7.7 Compliance 7

8.0 LIMITATIONS **7**

9.0 CLOSURE **8**

BORING LOCATION DIAGRAM ..... **Plate 1**

APPENDIX A
Definition of Terminology A-1
Method of Soil Classification A-2
Boring Log Notes A-3
Boring Logs ..... A-4 thru A-7

APPENDIX B
Laboratory Tests B-1

GEOTECHNICAL EVALUATION
LISBON CHANNEL TRAIL
SOUTHERN AVENUE TO TARPON AVENUE
RIO RANCHO, NEW MEXICO
WT JOB NO. 3227JJ055

1.0 PURPOSE

This report contains the results of our geotechnical evaluation for the proposed pedestrian trail, and was performed in general accordance with our contract. The purpose of our services is to provide information and recommendations regarding:

- Subsurface conditions
- Pavements
- Retaining walls
- Earthwork, including site preparation, fill placement, and suitability of existing soils for fill materials, and compaction

Results of the field exploration, field and laboratory tests are presented in the Appendices.

2.0 PROJECT DESCRIPTION

Project information supplied by Tyler J. Ashton, P.E. indicates that the project will consist of a paved pedestrian trail along Lisbon Channel. The project will also include retaining walls up to 4 feet in height. Should our assumptions not be correct, we should be notified immediately

3.0 SCOPE OF SERVICES

3.1 Field Exploration

Four borings were excavated drilled to a depth of 4 feet along the trail alignment. The borings were drilled at the approximate locations shown on the attached Boring Location Diagram. A field log was prepared for each boring. These logs contain visual classifications of the materials encountered during drilling as well as interpolation of the subsurface conditions between samples.

Final logs, included in Appendix A, represent our interpretation of the field logs and may include modifications based on laboratory observations and tests of the field samples. The final logs describe the materials encountered, their thicknesses, and the locations where samples were obtained.

The Unified Soil Classification System was used to classify soils. The soil classification symbols appear on the boring logs and are briefly described in Appendix A. Local and regional geologic characteristics were used to estimate the seismic design criteria.

3.2 Laboratory Analysis

Laboratory analyses were performed on representative soil samples to aid in material classification and to estimate pertinent engineering properties of the on-site soils for preparation of this report. The following tests were performed in general accordance with applicable procedures, and the results are presented in Appendix B.

- Field moisture content
- -#200 Sieve
- Liquid limit and plasticity index

3.3 Analyses and Report

Analyses were performed and this report was prepared for the exclusive purpose of providing geotechnical engineering and/or testing information and recommendations. The scope of services for this project does not include, either specifically or by implication, any environmental assessment of the Site or identification of contaminated or hazardous materials or conditions. If the owner is concerned about the potential for such contamination, other studies should be undertaken. We are available to discuss the scope of such studies with you.

This geotechnical engineering report includes a description of the project, a discussion of the field and laboratory testing programs, a discussion of the subsurface conditions, and design recommendations as required to satisfy the purpose previously described.

4.0 SITE CONDITIONS

4.1 Surface

At the time of our exploration, the Site was an existing unlined drainage channel in a residential area. The ground surface at the top of the channel was undulating and contained a moderate growth of weeds and shrubs**.** Site drainage trended to the south.

4.2 Subsurface

As presented on the boring logs, site soils within the depths explored consist of loose Silty SAND. Groundwater was not encountered in any of the borings at the time of exploration.

5.0 GEOTECHNICAL PROPERTIES & ANALYSIS

5.1 Laboratory Tests

Near-surface soils are granular Silty SANDS and are non-plastic. These soils are considered as good quality materials for supporting pavements.

6.0 RECOMMENDATIONS

6.1 General

Recommendations contained in this report are based on our understanding of the project criteria described in **Section 2.0**, and the assumption that the soil and subsurface conditions are those disclosed by the borings. Others may change the plans, final elevations, number and type of structures, foundation loads, and elevations during design or construction. Substantially different subsurface conditions from those described herein may be encountered or become known. Any changes in the project criteria or subsurface conditions shall be brought to our attention in writing.

6.2 Retaining Wall Design Criteria

Earth retaining structures less than 5 feet in height, above any free water surface, with level backfill and no surcharge loads may be designed using the equivalent fluid pressure method. Recommended equivalent fluid pressures and coefficients of base friction are:

- Active:
  Undisturbed subsoil.....35 psf/ft
  Compacted imported backfill .....30 psf/ft

- Passive
  Shallow wall footings.....250 psf/ft

- Coefficient of base friction 0.4*

  *The coefficient of base friction should be reduced to 0.3 when used in conjunction with passive pressure.

The lateral earth pressures presented herein do not include the lateral pressures arising from the presence of:

- Hydrostatic conditions, submergence or partial submergence
- Sloping backfill, positively or negatively
- Surcharge loading, permanent or temporary
- Seismic or dynamic conditions

Fill against footings, stem walls, and retaining walls should be compacted to densities specified in **EARTHWORK**. Compaction of each lift adjacent to walls should be accomplished with hand-operated tampers or other lightweight compactors. Over-compaction may cause excessive lateral earth pressures that could result in wall movements.

Retaining wall foundations may be proportioned utilizing an maximum allowable bearing pressure of 1,500 pounds per square foot for an embedment of 18 inches below lowest adjacent grade. A one third increase may be utilized for maximum toe pressures, although the entire foundation should remain in compression.

6.3 Pavements

The on-site soils are considered as good quality materials for support of pavements. The types of traffic anticipated to use the trail will be pedestrians and bicycles, along with an occasional city pick-up truck for maintenance purposes. Based upon these parameters, the resulting pavement section is 2 inches of asphalt concrete over properly prepared subgrade.

Normal maintenance, including crack sealing, slurry sealing, and/or chip sealing, should be performed during the life of the pavement.

Bituminous surfacing should be constructed of dense-graded, central plant-mix, asphalt concrete. Base course, portland cement, and asphalt concrete should conform with New Mexico Department of Transportation (NMDOT) or City of Rio Rancho specifications, mix designation of an SP-IV, with a maximum gyrations of 50.

Material and compaction requirements should conform to recommendations presented in the **Earthwork** section of this report. The gradient of paved surfaces should ensure positive drainage. Water should not pond in areas directly adjoining paved sections.

7.0 EARTHWORK

7.1 General

The conclusions contained in this report for the proposed construction are contingent upon compliance with recommendations presented in this section. Any excavating, trenching, or disturbance that occurs after completion of the earthwork must be backfilled, compacted and tested in accordance with the recommendations contained herein. It is not reasonable to rely upon our conclusions and recommendations if any future unobserved and untested trenching, earthwork activities or backfilling occurs.

7.2 Site Clearing

Strip and remove any existing vegetation, organic topsoils, debris, and any other deleterious materials from the retaining wall foundations and pavement areas. The building area is defined as that area within the building footprint plus two feet beyond

the perimeter of the footprint. All exposed surfaces should be free of mounds and depressions that could prevent uniform compaction.

7.3 Foundation Preparation

Specialized treatment of existing soils within foundation areas is not required. Footings should bear upon undisturbed native soils or engineered fill. Foundation excavations should be clean and free of any loose soil or debris.

7.4 Pavement Preparation

The subgrade should be scarified, moistened as required, and recompacted for a minimum depth of 10 inches prior to placement of fill and pavement materials.

7.5 Materials

Clean on-site native soils with low-expansive potentials or imported materials may be used as fill material for the following:

- Foundation areas
- Pavement areas
- Backfill

Imported soils should conform to the following:

- Gradation (ASTM C136):

	percent finer by weight
6"	100
4"	85-100
¾"	70-100
No. 4 Sieve	50-100
No. 200 Sieve	20 (max)

- Maximum soluble sulfates (%) 0.10
- Maximum Plasticity Index (PI) ..... Non-Plastic

Base course should conform to the City of Rio Rancho or NMDOT specifications.

7.6 Placement and Compaction

a. Place and compact fill in horizontal lifts, using equipment and procedures that will produce recommended water contents and densities throughout the lift.
b. Uncompacted fill lifts should not exceed 10 inches.
c. Frozen soil should not be used as fill and no fill should be placed over frozen ground.
d. Materials should be compacted to the following:

Material	Minimum Percent Compaction (ASTM D1557)
• On-site soil, reworked and fill	95
• Imported soil	95
• Nonstructural backfill	90

On-site and imported soils should be compacted within a water content range of two percent below to three percent above optimum.

7.7 Compliance

Recommendations for foundation and pavement elements supported on compacted fills or prepared subgrade depend upon compliance with **EARTHWORK** recommendations. To assess compliance, observation and testing should be performed under the direction of a geotechnical engineer.

8.0 LIMITATIONS

This report has been prepared assuming the project criteria described in **Section 2.0**. If changes in the project criteria occur, or if different subsurface conditions are encountered or become known, the conclusions and recommendations presented herein shall become invalid. In any such event, WT should be contacted in order to assess the effect that such variations may have on our conclusions and recommendations.

The recommendations presented are based entirely upon data derived from a limited number of samples obtained from widely spaced borings. The attached logs are indicators of subsurface conditions only at the specific locations and times noted. This report assumes the uniformity of the geology and soil structure between borings, however variations can and often do exist.

Whenever any deviation, difference or change is encountered or becomes known, WT should be contacted.

This report is for the exclusive benefit of our client alone. There are no intended third-party beneficiaries of our contract with the client or this report., and nothing contained in the contract or this report shall create any express or implied contractual or any other relationship with, or claim or cause of action for, any third party against WT.

This report is valid for the earlier of one year from the date of issuance, a change in circumstances, or discovered variations. After expiration, no person or entity shall rely on this report without the express written authorization of WT.

9.0 CLOSURE

We prepared this report as an aid to the designers of the proposed project. The comments, statements, recommendations and conclusions set forth in this report reflect the opinions of the authors. These opinions are based upon data obtained at the location of the borings, and from laboratory tests. Work on your project was performed in accordance with generally accepted standards and practices utilized by professionals providing similar services in this locality. No other warranty, express or implied, is made.

Created in TurboCAD LTE
(www.IMSIDesign.com)



Approximate Boring Location
Proposed Trail Location

NOT TO SCALE

Geotechnical Environmental Inspections Materials

Western Technologies Inc.
The Quality People
Since 1955

PROJECT:	**LISBON CHANNEL TRAIL**
JOB NO.:	**3227JJ055**

PLATE **1**

BORING LOCATION DIAGRAM

Allowable Soil Bearing Capacity	The recommended maximum contact stress developed at the interface of the foundation element and the supporting material.
Backfill	A specified material placed and compacted in a confined area.
Base Course	A layer of specified aggregate material placed on a subgrade or subbase.
Base Course Grade	Top of base course.
Bench	A horizontal surface in a sloped deposit.
Caisson/Drilled Shaft	A concrete foundation element cast in a circular excavation which may have an enlarged base (or belled caisson).
Concrete Slabs-On-Grade	A concrete surface layer cast directly upon base course, subbase or subgrade.
Crushed Rock Base Course	A base course composed of crushed rock of a specified gradation.
Differential Settlement	Unequal settlement between or within foundation elements of a structure.
Engineered Fill	Specified soil or aggregate material placed and compacted to specified density and/or moisture conditions under observations of a representative of a soil engineer.
Existing Fill	Materials deposited through the action of man prior to exploration of the site.
Existing Grade	The ground surface at the time of field exploration.
Expansive Potential	The potential of a soil to expand (increase in volume) due to absorption of moisture.
Fill	Materials deposited by the actions of man.
Finished Grade	The final grade created as a part of the project.
Gravel Base Course	A base course composed of naturally occurring gravel with a specified gradation.
Heave	Upward movement.
Native Grade	The naturally occurring ground surface.
Native Soil	Naturally occurring on-site soil.
Rock	A natural aggregate of mineral grains connected by strong and permanent cohesive forces. Usually requires drilling, wedging, blasting or other methods of extraordinary force for excavation.
Sand and Gravel Base Course	A base course of sand and gravel of a specified gradation.
Sand Base Course	A base course composed primarily of sand of a specified gradation.
Scarify	To mechanically loosen soil or break down existing soil structure.
Settlement	Downward movement.
Soil	Any unconsolidated material composed of discrete solid particles, derived from the physical and/or chemical disintegration of vegetable or mineral matter, which can be separated by gentle mechanical means such as agitation in water.
Strip	To remove from present location.
Subbase	A layer of specified material placed to form a layer between the subgrade and base course.
Subbase Grade	Top of subbase.
Subgrade	Prepared native soil surface.

©81WTI 091614

COARSE-GRAINED SOILS

LESS THAN 50% FINES

GROUP SYMBOLS	DESCRIPTION	MAJOR DIVISIONS
GW	WELL-GRADED GRAVEL OR WELL-GRADED GRAVEL WITH SAND, LESS THAN 5% FINES	GRAVELS MORE THAN HALF OF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE
GP	POORLY-GRADED GRAVEL OR POORLY-GRADED GRAVEL WITH SAND, LESS THAN 5% FINES	
GM	SILTY GRAVEL OR SILTY GRAVEL WITH SAND, MORE THAN 12% FINES	
GC	CLAYEY GRAVEL OR CLAYEY GRAVEL WITH SAND, MORE THAN 12% FINES	
SW	WELL-GRADED SAND OR WELL-GRADED SAND WITH GRAVEL, LESS THAN 5% FINES	SANDS MORE THAN HALF OF COARSE FRACTION IS SMALLER THAN NO. 4 SIEVE SIZE
SP	POORLY-GRADED SAND OR POORLY-GRADED SAND WITH GRAVEL, LESS THAN 5% FINES	
SM	SILTY SAND OR SILTY SAND WITH GRAVEL, MORE THAN 12% FINES	
SC	CLAYEY SAND OR CLAYEY SAND WITH GRAVEL, MORE THAN 12% FINES	

NOTE: Coarse-grained soils receive dual symbols if they contain 5% to 12% fines (e.g., SW-SM, GP-GC).

FINE-GRAINED SOILS

MORE THAN 50% FINES

GROUP SYMBOLS	DESCRIPTION	MAJOR DIVISIONS
ML	SILT, SILT WITH SAND OR GRAVEL, SANDY SILT, OR GRAVELLY SILT	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50
CL	LEAN CLAY OF LOW TO MEDIUM PLASTICITY, SANDY CLAY, OR GRAVELLY CLAY	
OL	ORGANIC SILT OR ORGANIC CLAY OF LOW TO MEDIUM PLASTICITY	
MH	ELASTIC SILT, SANDY ELASTIC SILT, OR GRAVELLY ELASTIC SILT	SILTS AND CLAYS LIQUID LIMIT MORE THAN 50
CH	FAT CLAY OF HIGH PLASTICITY, SANDY FAT CLAY, OR GRAVELLY FAT CLAY	
OH	ORGANIC SILT OR ORGANIC CLAY OF HIGH PLASTICITY	
PT	PEAT AND OTHER HIGHLY ORGANIC SOILS	HIGHLY ORGANIC SOILS

NOTE: Fine-grained soils may receive dual classification based upon plasticity characteristics (e.g. CL-ML).

SOIL SIZES

COMPONENT	SIZE RANGE
BOULDERS	Above 12 in.
COBBLES	3 in. – 12 in.
GRAVEL	No. 4 – 3 in.
Coarse	¾ in. – 3 in.
Fine	No. 4 – ¾ in.
SAND	No. 200 – No. 4
Coarse	No. 10 – No. 4
Medium	No. 40 – No. 10
Fine	No. 200 – No. 40
Fines (Silt or Clay)	Below No. 200

NOTE: Only sizes smaller than three inches are used to classify soils

CONSISTENCY

CLAYS & SILTS	BLOWS PER FOOT
VERY SOFT	0 – 2
SOFT	3 – 4
FIRM	5 – 8
STIFF	9 – 15
VERY STIFF	16 – 30
HARD	OVER 30

RELATIVE DENSITY

SANDS & GRAVELS	BLOWS PER FOOT
VERY LOOSE	0 – 4
LOOSE	5 – 10
MEDIUM DENSE	11 – 30
DENSE	31 – 50
VERY DENSE	OVER 50

NOTE: Number of blows using 140-pound hammer falling 30 inches to drive a 2-inch-OD (1⅜-inch ID) split-barrel sampler (ASTM D1586).

PLASTICITY OF FINE GRAINED SOILS

PLASTICITY INDEX	TERM
0	NON-PLASTIC
1 – 7	LOW
8 – 20	MEDIUM
Over 20	HIGH

DEFINITION OF WATER CONTENT

DRY
SLIGHTLY DAMP
DAMP
MOIST
WET
SATURATED

©81 WTI
090414

The number shown in **"BORING NO."** refers to the approximate location of the same number indicated on the "Boring Location Diagram" as positioned in the field by pacing or measurement from property lines and/or existing features, or through the use of Global Positioning System (GPS) devices. The accuracy of GPS devices is somewhat variable.

"DRILLING TYPE" refers to the exploratory equipment used in the boring wherein **HSA = hollow stem auger**, and the dimension presented is the outside diameter of the HSA used.

"N" in "BLOW COUNTS" refers to a 2-inch outside diameter split-barrel sampler driven into the ground with a 140 pound drop-hammer dropped 30 inches repeatedly until a penetration of 18 inches is achieved or until refusal. The number of blows, or "blow count", of the hammer is recorded for each of three 6-inch increments totaling 18 inches. The number of blows required for advancing the sampler for the last 12 inches (2nd and 3rd increments) is defined as the Standard Penetration Test (SPT) "**N**"-Value. Refusal to penetration is considered more than 50 blows per 6 inches. (Ref. ASTM D1586).

"R" in "BLOW COUNTS" refers to a 3-inch outside diameter ring-lined split barrel sampler driven into the ground with a 140 pound drop-hammer dropped 30 inches repeatedly until a penetration of 12 inch is achieved or until refusal. The number of blows required to advance the sampler 12 inches is defined as the "**R**" blow count. The "**R**" blow count requires an engineered conversion to an equivalent SPT N-Value. Refusal to penetration is considered more than 50 blows per foot. (Ref. ASTM D3550).

"CS" in "BLOWS/FT." refers to a 2½-in. outside diameter California style split-barrel sampler, lined with brass sleeves, driven into the ground with a 140-pound hammer dropped 30 inches repeatedly until a penetration of 18 inches is achieved or until refusal. The number of blows of the hammer is recorded for each of the three 6-inch increments totaling 18 inches. The number of blows required for advancing the sampler for the last 12 inches (2nd and 3rd increments) is defined as the "CS" blow count. The "CS" blow count requires an engineered conversion to an equivalent SPT N-Value. Refusal to penetration is considered more than 50 blows for a 6-inch increment. (Ref. ASTM D 3550)

"SAMPLE TYPE" refers to the form of sample recovery, in which **N** = Split-barrel sample, **R** = Ring-lined sample, **"CS"** = California style split-barrel sample, **G** = Grab sample, **B** = Bucket sample, **C** = Core sample (ex. diamond bit rock coring).

"DRY DENSITY (LBS/CU FT)" refers to the laboratory-determined dry density in pounds per cubic foot. The symbol **"NR"** indicates that no sample was recovered.

"WATER (MOISTURE) CONTENT" (% of Dry Wt.) refers to the laboratory-determined water content in percent using the standard test method ASTM D2216.

"USCS" refers to the "Unified Soil Classification System" Group Symbol for the soil type as defined by ASTM D2487 and D2488. The soils were classified visually in the field, and where appropriate, classifications were modified by visual examination of samples in the laboratory and/or by appropriate tests.

These notes and boring logs are intended for use in conjunction with the purposes of our services defined in the text. Boring log data should not be construed as part of the construction plans nor as defining construction conditions.

Boring logs depict our interpretations of subsurface conditions at the locations and on the date(s) noted. Variations in subsurface conditions and characteristics may occur between borings. Groundwater levels may fluctuate due to seasonal variations and other factors.

The stratification lines shown on the boring logs represent our interpretation of the approximate boundary between soil or rock types based upon visual field classification at the boring location. The transition between materials is approximate and may be more or less gradual than indicated.

©81WTI
091614

DATE DRILLED: **2-6-17**
LOCATION: **See Location Diagram**
ELEVATION: **Not Determined**

BORING NO. 1

EQUIPMENT TYPE: **Hand Auger**
DRILLING TYPE: **3"**
FIELD ENGINEER: **K. Newberry**

MOISTURE CONTENT (% OF DRY WT.)	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	DEPTH (FEET)	USCS	GRAPHIC	SOIL DESCRIPTION
7.5		G				SP-SM		Poorly Graded SAND, with Silt; light brown, loose, moist
								BORING TERMINATED AT 4 FEET

N- STANDARD PENETRATION TEST
R- RING SAMPLE
NR- NO SAMPLE RECOVERY
G- GRAB SAMPLE
B- BUCKET SAMPLE

NOTES: **Groundwater Not Encountered**

THIS SUMMARY APPLIES ONLY AT THIS LOCATION AND AT THE TIME OF LOGGING. CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH TIME. DATA PRESENTED IS A SIMPLIFICATION.

Geotechnical Environmental Inspections Materials
Western Technologies Inc.
The Quality People
Since 1955

PROJECT: **LISBON CHANNEL TRAIL**
JOB NO.: **3227JJ055**

PLATE **A-4**

BORING LOG

DATE DRILLED: **2-6-17**
LOCATION: **See Location Diagram**
ELEVATION: **Not Determined**

BORING NO. 2

EQUIPMENT TYPE: **Hand Auger**
DRILLING TYPE: **3"**
FIELD ENGINEER: **K. Newberry**

MOISTURE CONTENT (% OF DRY WT.)	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	DEPTH (FEET)	USCS	GRAPHIC	SOIL DESCRIPTION
		G				SP-SM		Poorly Graded SAND, with Silt; light brown, loose, moist
								more sand, dry
								BORING TERMINATED AT 4 FEET

N- STANDARD PENETRATION TEST
R- RING SAMPLE
NR- NO SAMPLE RECOVERY
G- GRAB SAMPLE
B- BUCKET SAMPLE

NOTES: **Groundwater Not Encountered**

THIS SUMMARY APPLIES ONLY AT THIS LOCATION AND AT THE TIME OF LOGGING. CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH TIME. DATA PRESENTED IS A SIMPLIFICATION.

Geotechnical Environmental Inspections Materials
Western Technologies Inc.
The Quality People
Since 1955

PROJECT: **LISBON CHANNEL TRAIL**
JOB NO.: **3227JJ055**

PLATE **A-5**

BORING LOG

DATE DRILLED: **2-6-17**
LOCATION: **See Location Diagram**
ELEVATION: **Not Determined**

BORING NO. 3

EQUIPMENT TYPE: **Hand Auger**
DRILLING TYPE: **3"**
FIELD ENGINEER: **K. Newberry**

MOISTURE CONTENT (% OF DRY WT.)	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	DEPTH (FEET)	USCS	GRAPHIC	SOIL DESCRIPTION
5.0		G				SM		Silty SAND; light brown, loose, moist
								medium dense, damp
								BORING TERMINATED AT 4 FEET

N- STANDARD PENETRATION TEST
R- RING SAMPLE
NR- NO SAMPLE RECOVERY
G- GRAB SAMPLE
B- BUCKET SAMPLE

NOTES: **Groundwater Not Encountered**

THIS SUMMARY APPLIES ONLY AT THIS LOCATION AND AT THE TIME OF LOGGING. CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH TIME. DATA PRESENTED IS A SIMPLIFICATION.

Geotechnical Environmental Inspections Materials
Western Technologies Inc.
The Quality People
Since 1955

PROJECT: **LISBON CHANNEL TRAIL**
JOB NO.: **3227JJ055**

PLATE **A-6**

BORING LOG

DATE DRILLED: **2-6-17**
LOCATION: **See Location Diagram**
ELEVATION: **Not Determined**

BORING NO. 4

EQUIPMENT TYPE: **Hand Auger**
DRILLING TYPE: **3"**
FIELD ENGINEER: **K. Newberry**

MOISTURE CONTENT (% OF DRY WT.)	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	DEPTH (FEET)	USCS	GRAPHIC	SOIL DESCRIPTION
1.6		G				SP		Poorly Graded SAND; light brown, loose, moist
								medium dense, damp
								dry, very sandy
								BORING TERMINATED AT 4 FEET

N- STANDARD PENETRATION TEST
R- RING SAMPLE
NR- NO SAMPLE RECOVERY
G- GRAB SAMPLE
B- BUCKET SAMPLE

NOTES: **Groundwater Not Encountered**

THIS SUMMARY APPLIES ONLY AT THIS LOCATION AND AT THE TIME OF LOGGING. CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH TIME. DATA PRESENTED IS A SIMPLIFICATION.

Geotechnical Environmental Inspections Materials
Western Technologies Inc.
The Quality People
Since 1955

PROJECT: **LISBON CHANNEL TRAIL**
JOB NO.: **3227JJ055**

PLATE **A-7**

BORING LOG

Boring No.	Depth (ft.)	USCS Class.	Initial Dry Density (pcf)	Initial Water Content (%)	Compression Properties			Expansion Properties		Plasticity		Percent Passing #200	Soluble Sulfate (ppm)	Remarks
					Surcharge (ksf)	Total Compression (%)		Surcharge (ksf)	Expansion (%)	Liquid Limit	Plasticity Index			
						In-Situ	After Saturation							
1	0-5	SP-SM		7.5							NP	10		
3	0-5	SM		5.0							NP	18		
4	0-5	SP		1.6							NP	5		

Note: Initial Dry Density and Initial Water Content are in-situ values unless otherwise noted.
NP = Non-Plastic

Remarks

1. Compacted density (approx. 95% of ASTM D1557 max. density at moisture content slightly below optimum.)
2. Submerged to approximate saturation.
3. Slight rebound after saturation.
4. Sample disturbance observed.

Geotechnical Environmental Inspections Materials

Western Technologies Inc. The Quality People Since 1955

wt-us.com

PROJECT: LISBON CHANNEL TRAIL
JOB NO.: 3227JJ055

SOIL PROPERTIES

PLATE

B-1