

Unit Price Bid Proposal

Modified with Addendum 01 – 10/21/2026

ITEM	ITEM DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT	SPECIFICATION
1	MOBILIZATION, CIP.	LS	1			SSCAFCA 1503
2	CONSTRUCTION STAKING, CIP	LS	1			SSCAFCA 1513
3	NPDES PERMIT, CIP.	LS	1			SSCAFCA 1511
4	PROTECTION OF PROJECT FROM WATER DURING CONSTRUCTION, CIP.	LS	1			SSCAFCA 1512
5	CONSTRUCTION TRAFFIC CONTROL & BARRICADING, CIP.	LS	1			APWA 1200
6	CONSTRUCTION PROJECT SIGN	EA	2			Plans
7	UTILITY ALLOWANCE, CIP.	AL	1	25,000.00	25,000.00	SSCAFCA 668
8	CLEARING AND GRUBBING, CIP.	AC	2.2			APWA 201 & STS 201
9	TESTING ALLOWANCE, CIP.	AL	1	40,000.00	40,000.00	SSCAFCA 1507
10	REMOVE AND DISPOSE EXISTING STRUCTURES AND OBSTRUCTIONS (MISC ITEMS IN CHANNEL INC. CONC.), CIP.	LS	1			SSCAFCA 1515
11	UNCLASSIFIED EXCAVATION, CIP.	CY	1,032			SSCAFCA 1510
12	BORROW, CIP.	CY	2,582			SSCAFCA 1510
13	SAWCUT CONCRETE, REMOVE AND DISPOSE, CIP.	LS	1			NMDOT 450
14	SLOPE STABILIZATION AND SEEDING, GRAVEL MULCH, CIP.	AC	0.06			COA 1013
15	SLOPE STABILIZATION AND SEEDING, ANGULAR AGGREGATE, CIP.	AC	0.11			COA 1013
16	NATIVE/GRASS SEEDING, CIP.	AC	0.27			STS1012/APWA 1012
17	6" SHOTCRETE FOR CHANNEL 4000 PSI INCL. REINF + SUBGRADE PREPARATION, CIP	SY	6,200			NMDOT 519

ITEM	ITEM DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT	SPECIFICATION
18	6" C900 PVC WATER LINE PIPE, EXCLUDES FITTINGS, INCL. TRACER WIRE, TRENCH & COMPACTED BACKFILL UP TO 6' DEEP, REPLACEMENT OF C&G AND ASPHALT IN KIND, INCL. FITTINGS, CIP	LF	20			APWA 801
19	FIRE HYDRANT, INCL. BLOCKING, AGGREGATE, GATE VALVE WITH BOX COVER, FITTINGS, TAPPING SADDLE, AND TRACE WIRE BOX, CIP	EA	1			W15 CORR STD
20	REMOVE AND RESET HANDRAIL EXISTING, INCL. REPAINTING, CIP	FT	150			SEE PLANS
21	6" REINFORCED CONCRETE RUNDOWN, DRIVE PAD, SIDEWALK 4000 PSI INCL. REINF + SUBGRADE PREPARATION, CIP	SY	320			NMDOT 515
BASE BID TOTAL (Items 1-21)				\$		
NMGRT 7.4375%				\$		
CONSTRUCTION TOTAL				\$		

- Unit Price Bid Proposal End -